



1, क्वीन्स वे, कोलकाता - 700 071

1, Queen's Way, Kolkata - 700 071

विक्टोरिया मेमोरियल हाल

VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण के तहत एक स्वायत्त संगठन)

(An autonomous organisation under the administrative control of the Ministry of Culture, Govt. of India)

VM No. 364 /VC-06/11

Date: 11.03.2021

Notice Inviting Tender

Sealed Tenders are invited by the Victoria memorial Hall from licensed electrical contractors for the work as mentioned below:

Name of Work:

Renovation of pathway lights at Eastern side of VM garden of Victoria Memorial Hall, Kolkata . (Work Schedule enclosed vide Annexure – 1)

The Sealed tenders addressed to the Secretary & Curator, Victoria Memorial Hall, 1 – Queens Way, Kolkata 700071, should be dropped in the tender box kept for the purpose in the office of the undersigned on or before 2:00 pm on 21.03.2021. The Tenders will be opened on the same day at 2:30 pm in the presence of such tenderers or their representatives who wish to remain present.

Tenders in sealed cover should be superscribed "Renovation of pathway lights at Eastern side of VM garden of Victoria Memorial Hall, Kolkata".

Rates so quoted will remain valid for six months.

Rates should be quoted inclusive of taxes (mentioning the tax rate) and transportation charges etc. The rate should be quoted both in words and figures. The tenderers should clearly state the delivery schedule. The job should be completed within 10 days from the date of receipt of Work Order.

Tenders should be submitted on the letterhead of the firm.

The tenderers should have sufficient experience in doing similar nature of jobs preferably in Govt. Sector. The tenderers should submit photocopies of their licences, PAN card and papers in support of their work experience.

The tenderers will be required to Sign "Bid Security Declaration" on their respective letter head accepting that if they withdraw or modify their bids during the period of bid validity etc, they will be suspended for the time of One (01) year from participating in any tender called by VMH.

The successful tenderer will be required to deposit 10% of the total work value as Security Deposit in the form of Demand Draft issued in favour of "Victoria Memorial Hall" drawn from any commercial bank payable at Kolkata before receiving of Work Order. The security money since deposited will be refunded not earlier than six month from the date of completion of the job.

☎ : 2223-1890/1891/0953/5142 • फैक्स/Fax : +91-33-2223-5142

ई-मेल/E-mail : victomem@gmail.com • वेबसाइट/Website : www.victoriameorial-cal.org



1, क्वीन्स वे, कोलकाता - 700 071
1, Queen's Way, Kolkata - 700 071

विक्टोरिया मेमोरियल हाल

VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण
के तहत एक स्वायत्त संगठन)

(An autonomous organisation under the administrative control
of the Ministry of Culture, Govt. of India)

The job executed by the successful tenderer shall have to be guaranteed against bad workmanship for a period of six (6) months from the date of completion of the job. If any defect is detected during the period as mentioned above, he will be liable to rectify the same free of cost within reasonable time. Otherwise, VMH will get it rectified at its own cost and adjust the same from the Security Deposit.

The job to be executed is scheduled to be inspected by the concerned unit of the VMH.

The job to be executed will follow the Govt. specification.

For any additional information, tenderers may contact the Electrician of this office between 2:00 pm to 4:00 pm on any working day.

The authority reserves the right to accept or reject any or all the tenders without assigning any reason thereof.

Encl: One Schedule of Work


Secretary & Curator

Copies along with Schedules of Work forwarded to the Security Officer for kind information and Shri Dipankar Samantha with request to insert the NIT in our website .


Secretary & Curator

☎ : 2223-1890/1891/0953/5142 • फैक्स/Fax : +91-33-2223-5142

ई-मेल/E-mail : victomem@gmail.com • वेबसाइट/Website : www.victoriame-morial-cal.org

SCHEDULE OF WORK

Renovation of pathway lights at Eastern side of VM garden of Victoria Memorial

Sl. No.	Description	Qty	Rate	Unit	Amount
01	Dismantling and disconnection of broken, damaged bollard light fittings and cable end boxes at different position in the garden at East Gate pathway to eastern pond of VM garden, as required.	01 Job		Job	
02	Unearthing the cable leads and relaying of following size PVC, insulated and PVC sheathed XLPE armoured aluminium conductor cable of 1.1 KV grade covering and refitting the trench etc, as required.	90 Mtrs		Mtrs	
03	Supply and fixing of single door MS junction box size 8"(H) x 6"(W) x 5"(D) having fabricated with 16 SWG MS sheet i/c locking arrangement 4 way DMC terminal, Din bar for S &F 6A SP MCB completed with shynthetic enamel paint over one coat of primer, i/c grouting the C.C. foundation 450 mm below the ground level by the help of 02 nos. 25 mm x 25 mm x 6 mm M.S. Angle, 600 mm length and proper welded in junction box, as required.	38 Nos.		Each	
04	Supply and laying of 1.5 sqmm, 03 core insulated sheathed flexible cable in existing loop box to bollard fittings aprox length 02 mtrs by DWC pipe direct in ground i/c excavation and refilling the trench etc, as required.	38 Jobs		Job	
05	Supplying, Laying & Commisioning of PVC insulated and sheathed/ XLPE power cable of 1.1 KV grade direct in ground i/c excavation, protective covering(without sand cushioning) and refilling the trench etc, as required. a. 4 Core, 10 sqmm,	76 mtrs		Mtr	
06	Supply and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/ XLPE Alluminium conductor cable of 1.1 KV grade, as required. a. 4 core, 10 sqmm	76 Sets		Set	
07	Installation, testing and commissioning of Bollards light fitting on the C.C. foundation size 400 m x 400 mm x 600 mm below the ground level and 200 mm x 200 mm x 450 mm above the ground level and top of the colomun 04 nos. stay rod with double nut and washer for fixing the light fitting i/c net cementing the post column , as required	38 Jobs		Job	