



1, क्वीन्स वे, कोलकाता - 700 071  
1, Queen's Way, Kolkata - 700 071

# विक्टोरिया मेमोरियल हल

## VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण  
के तहत एक स्वायत्त संगठन)  
(An autonomous organisation under the administrative control  
of the Ministry of Culture, Govt. of India)

VM no. 981 /2021

28.09.2021

### Tender notice

Victoria Memorial, 1 Queens Way, Kolkata 700071 (2223-0953) invites tender from the reputed/experienced Govt contractors having proper work license for providing & laying of synthetic turf etc. (as per sample) at the light and sound area(as per scope of work). The tender in sealed cover should be supercribed with "Tender for providing & laying of synthetic turf etc. at the light and sound area" must be sent to the office of the Secretary & Curator, Victoria Memorial Hall within 01 p.m. on 04.10.2021. Tenderers are to submit papers about their experience in similar nature of works, Pan Card, GST certificate etc. (all photo copies) alongwith tenders.

The tender will be opened on the same day at 3.00 p.m. at the chamber of the Accounts Officer.

The rate should be inclusive of labour charges, materials and transportation, GST. The rate should be quoted both in words and figures. The successful tenderer will be required to complete the job within 10 days of the receipt of the order. The work should be done with good quality ISI marked materials and weather coat paint and synthetic turf (as per sample) under the supervision of the Security Officer & Caretaker.

On award of work, the selected agency has to deposit 3% of the work value in the form of bank draft as performance security.

The details of works may be verified first in consultation with VM officials and thereafter quotation may be submitted.

VMH reserves the right of rejection of any or all tenders without assigning any reason.

  
Secretary & Curator

### SCOPE OF WORK

**NAME OF WORK : Widening of surrounding approach concrete pathways and providing synthetic grass turving at open platform for light & sound system at Victoria Hall premises, Kolkata**

page-1

SI No	Description of Items	Unit	Quantity	Rate (Rs.)	Amount(Rs.)	Remarks
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil	Cum	21.42			
2	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	Cum	10.20			
3	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.	Sqm	34			
4	Cement concrete pavement with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), including finishing complete.	Cum	4.08			
5	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	Sqm	116.00			
6	Providing and laying in position bitumen hot sealing compound for expansion joints etc. Using grade 'A' sealing compound. (per cm depth per cm width per metre length)	Metre	80.00			



Sl No	Description of Items	Unit	Quantity	Rate (Rs.)	Amount(Rs.)	Remarks
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.	Kg	40.00			
	Hard drawn steel wire fabric (3mm wire @ 200c/c, b/ways)					
8	Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete	Sqm	7.00			
9	Providing and fixing at or near ground level precast cement concrete in kerbs, edgings etc. as per approved pattern and setting in position with cement mortar 1:3 (1 Cement : 3 coarse sand), including the cost of required centering, shuttering complete.	Cum	0.40			
	1:1½:3 (1 Cement: 1½ coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size).					
10	Providing and laying with adhesive synthetic grass or artificial turfing (15 to 20 mm)of standard make including cutting and shaping and placing in existing position on hard concrete surface with necessary tools and tackles complete.	Sqm	250.00			
11	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads	cum	5.00			
12	Painting with best quality weather cote with primar	Sqm	96.3			
				Total =		
				Say		