



1. क्वीन्स वे, कोलकाता - 700 071
1. Queen's Way, Kolkata - 700 071

विक्टोरिया मेमोरियल हॉल VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण
के तहत एक स्वायत्त संगठन)
(An autonomous organisation under the administrative control
of the Ministry of Culture, Govt. of India)

VM No. 1685 /XX-5/2008(Part-I)

Date: 14/12/2022

Notice Inviting Tender

Sealed Tenders are invited by the Victoria memorial Hall from licensed electrical contractors for the work as mentioned below:

Name of Work:

“Supply, Fixing and Fitting of rain shed sheet etc for dehumidifier machines at Victoria Memorial Hall, Kolkata”. (Schedule of Quantities & Drawing enclosed vide Annexure – 1)

The Sealed tenders addressed to the Secretary & Curator, Victoria Memorial Hall, 1 – Queens Way, Kolkata 700071, should be dropped in the tender box kept for the purpose in the office of the undersigned on or before 2:00 pm on 30/12/2022. The Tenders will be opened on the same day at 2:30 pm in the presence of such tenderers or their representatives who wish to remain present.

Tenders in sealed cover should be superscribed “Supply, Fixing and Fitting of rain shed sheet etc for dehumidifier machines at Victoria Memorial Hall, Kolkata”.

Rates so quoted will remain valid for six months.

Rates should be quoted inclusive of taxes (mentioning the tax rate) and transportation charges etc. The rate should be quoted both in words and figures. The tenderers should clearly state the delivery schedule. The job should be completed within 10 days from the date of receipt of Work Order.

Tenders should be submitted on the letterhead of the firm.

The tenderers should have sufficient experience in doing similar nature of jobs preferably in Govt. Sector. The tenderers should submit photocopies of their licences, PAN card, GSTIN (GSTR-1, GSTR-3B) documents and papers in support of their work experience.

The tenderers excepting those who are exempted from furnishing EMD as per G.O.I. Order (photo copy to be furnished) will be required to deposit 2% of the quoted rates as Earnest Money in the form of Demand Drafts in favour of the “Victoria Memorial Hall”, drawn from any commercial bank, payable at Kolkata. The above earnest money will be refunded after one month from the date of issuance of Work Order. The EMD's of unsuccessful tenderers shall be released after the issuance of work order or latest by one month.

☎ : 2223-1890 / 1891/0953/5142 • फ़ैक्स / Fax : +91-33-2223-5142

ई-मेल / E-Mail : Victomem@gmail.com • वेबसाइट / Website: www.victoriamemorial-cal.org



1. क्वीन्स वे, कोलकाता - 700 071
1. Queen's Way, Kolkata - 700 071

विक्टोरिया मेमोरियल हाल VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण
के तहत एक स्वायत्त संगठन)
(An autonomous organisation under the administrative control
of the Ministry of Culture, Govt. of India)

The successful tenderer will be required to deposit 3% of the total work value as Security Deposit in the same form in which the Earnest money has been deposited to

the Victoria Memorial Hall before receiving of Work Order. The security money since deposited will be refunded not earlier than eight months from the date of completion of the job. The earnest money will be forfeited if the Security Money is not deposited within seven days from the date of intimation in this regard or if the successful tenderer is unable to commence the job within specified time.

The job executed by the successful tenderer shall have to be guaranteed against bad workmanship for a period of six (6) months from the date of completion of the job. If any defect is detected during the period as mentioned above, he will be liable to rectify the same free of cost within reasonable time. Otherwise, VMH will get it rectified at its own cost and adjust the same from the Security Deposit.

The job to be executed is scheduled to be inspected by the concerned unit of the VMH.

The job to be executed will follow the Govt. specification.

For any additional information, tenderers may contact the In-charge Electric Unit of this office between 2:00 pm to 4:00 pm on any working day.

The authority reserves the right to accept or reject any or all the tenders without assigning any reason thereof.

Encl: One Schedule of Work and Drawing


Secretary & Curator

Copies along with Schedules of Quantities & Drawing forwarded to the Security Officer for kind information and Shri Dipankar Samantha with request to insert the NIT in our website .


Secretary & Curator

☎ : 2223-1890 / 1891/0953/5142 • फैक्स / Fax : +91-33-2223-5142

ई-मेल / E-Mail : Victomem@gmail.com • वेबसाइट / Website: www.victoriamemorial-cal.org

General Terms and Conditions:

Photo copies to be attached with the tender:

1. Profit and loss Account of last 03 years with Chartered Accountant's signature with registration number and official seal.
2. 03 nos. of certificate of completion of similar type of work.
3. Copy of Govt. enlistment with Govt of India or Govt of W.B.
4. Declaration of termination of Contract, if failed to complete the work within scheduled time.



SCHEDULE OF QUANTITIES

Name of work : Supply fixing and fitting of rain shed with precoated sheet etc. For Denitrifier machines at Victoria Memorial Hall, Kolkata 2022-23.

SI No.	Description of Items	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources).	Cum	1.00		
2	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :				
2.1	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	Cum	2.20		
3	Centering and shuttering including strutting, propping etc. and removal of form for				
3.1	Foundations, footings, bases of columns, etc. for mass concrete.	Sqm	26.00		
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
4.1	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	140.00		
5	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				
5.1	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	Kg	857.00		
6	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineerin- charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm	67.00		

7	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete :				
7.1	Barge board (Upto 300 mm).	Mtr	18.00		
8	Applying priming coat:				
8.1	With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works.	Sqm	175.00		
9	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface etc. complete.				
9.1	On steel work.	Sqm	175.00		
10	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes				
10.1	110 mm diameter.	Mtr	15.00		
11	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion				
11.1	Bend 87.5°				
11.1.1	110 mm bend.	Each	2.00		
11.2	Shoe (Plain)				
11.2.1	110 mm Shoe.	Each	4.00		

Total:- 0.00

Say Total:- 0.00

Amount In Words:-

PK

Supply fixing and fitting of train shed etc for Dehumidifier machine of Victoria Memorial Hall, Kolkata

