



1, क्वीन्स वे, कोलकाता - 700 071  
1, Queen's Way, Kolkata - 700 071

# विक्टोरिया मेमोरियल हाल

## VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण  
के तहत एक स्वायत्त संगठन)

(An autonomous organisation under the administrative control  
of the Ministry of Culture, Govt. of India)

VMNo.

640 /2023

Date 28.08.2023

### Tender Notice

Victoria Memorial Hall, 1 Queen's Way, Kolkata 700071 (2223 0953) invites tender from the reputed/experienced civil contractors for repair and renovation of CISF office at Victoria Memorial premises (as per scope of works). The tender in sealed cover should be superscribed with "Tender for repair and renovation of CISF office" must be sent to the office of the Secretary & Curator, Victoria Memorial Hall within 02 p.m. on 08.09.2023. Tenderers are to submit papers about their experience, Pan Card, GST certificate, Trade licence, Audited Accounts of last three years (all photo copies) alongwith tenders.

The tenders will be opened on the same day at 2.30 p.m. in the chamber of the Accounts officer. Tenderers/their representatives may remain present at the time of opening of tender if they so desire.

The tender should be accompanied by an EMD of Rs.2,000.00 (Rupees two thousand only) of the estimated value of the contract in the form of an a/c payee Demand Draft drawn in favour of "Victoria Memorial Hall" payable at Kolkata. However the tenderers who are exempted from furnishing EMD as per GOI orders need not furnish EMD, subject to submission of necessary supporting papers. The Successful bidder will have to deposit performance security @ 5% of the estimated value of the contract, which should remain valid for a period of sixty days beyond the date of completion of all contractual obligations of the agency.

The rate should be submitted in the prescribed format. The rates inclusive of taxes & charges should be quoted both in words and figures. The rate quoted will be valid for six months. The successful tenderer will be required to complete the job within 10 days of the receipt of the order. The work should be done with good quality ISI marked materials under the supervision of the Caretaker. Tenderers may inspect the site on any working day, during working hours before submission of tenders.

VMH reserves the right of rejection of any or all tenders without assigning any reason

  
Secretary & Curator

Copy forwarded:

The Accounts Officer, VM

Shri Dipankar Samanta, He is requested to get the matter published on VM website.

  
Secretary & Curator

## ESTIMATE

To  
The Secretary & Curator  
Victoria Memorial Hall  
Kolkata – 700071

ABSTRACT OF COST						
Name of Work : Upgradation to CISF office at VMH, Kolkata, during 2023-24.						
Item No.	DSR'21 Item no.	Description of Items	Quantity	unit	Rate	Amount
		<b>1. REPAIRS TO BUILDING</b>				
1.1	9.101	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete.				
1.1.1	9.101.2	Twin rubber stopper	3.00	each		
		<b>2. FINISHING</b>				
2.1	13.42	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required colour to give an even shade :				
2.1.1	13.42.1	Two or more coats on new work	180.00	sqm		
2.2	13.62	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
2.2.1	13.62.1	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	10.00	Sqm		
2.3	13.68	French spirit polishing :				
2.3.1	13.68.1	Two or more coats on new works including a coat of wood filler	10.00	sqm		
2.40	13.91	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	180.00	sqm		
		<b>3. DISMANTLING AND DEMOLISHING</b>				
3.1	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	5.00	Cum		
		<b>4. NEW TECHNOLOGIES AND MATERIALS</b>				



Item No.	DSR'21 Item no.	Description of Items	Quantity	unit	Rate	Amount
4.1	26.22	Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595mm of approved texture, design and patterns as per CPWD Specification 2019, to be laid in true horizontal level suspended on inter-locking metal T-Grid of hot dipped galvanised iron section of 0.33mmthick (galvanized @ 120 grams per sqm including both sides)comprising of main-T runners of size 24x38 mm of length 3000 mm,cross - T of size 24x32 mm of length 1200 mm and secondary intermediate cross-T of size 24x32 mm of length 600mm to formgrid module of size 600 x 600 mm, suspended from ceiling usinggalvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 12x50 mm long dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 76x25x25x1.6 mm fixed with grid and Z cleat of size 25x37x25x1.6mm thick with precut hole on both 25mm flange to pierce into 12x50mm or even bigger size dash fastener if require, fixed with Glavanised iron perimeter wall angle or size 24x24x0.40 mm of length 3000 mm to be fixed on periphey wall / partition with the help of plastic rawl plugs at 450mm center to center and 40 mm long dry wall S.S screws. The workshall be carried out as per specifications, drawing and as per directions of the Engineer in Charge				
4.1.1	26.22.1	With 15 mm thick Tegular edged light weight calcium silicate false ceiling tiles	2.16	sqm		