



1, क्वीन्स वे, कोलकाता - 700 071  
1, Queen's Way, Kolkata - 700 071

**विक्टोरिया मेमोरियल हाल**  
**VICTORIA MEMORIAL HALL**  
(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण  
के तहत एक स्वायत्त संगठन)  
(An autonomous organisation under the administrative control  
of the Ministry of Culture, Govt. of India)

VM No.

365/VC-11/2004

Date: 27-02-2024

### Notice Inviting Tender

Sealed Tenders are invited by the Victoria memorial Hall from licensed electrical contractors for the work as mentioned below:

Name of Work:

“Supply, laying and fixing of 200 sqmm underground armoured aluminium cable from T1 switch room to T1 panel located inside the Victoria Memorial building premises, Kolkata, during 2023-24.” (Schedule of Work enclosed vide Annexure – 1)

The Sealed tenders on the Letter Head of the firm and addressed to the Secretary & Curator, Victoria Memorial Hall, 1 – Queens Way, Kolkata 700071, should be dropped in the tender box kept for the purpose in the office of the undersigned on or before 2:00 pm on 12.03.24. The Tenders will be opened on the same day at 2:30 pm in the presence of such tenderers or their representatives who wish to remain present.

Tenders in sealed cover should be superscribed “Supply, laying and fixing of 150 sqmm underground armoured aluminium cable T1 from switch room to T1 panel located inside the Victoria Memorial building premises, Kolkata, during 2023-24.”

Rates so quoted will remain valid for six months.

Rates should be quoted inclusive of taxes (mentioning the tax rate) and transportation charges etc. The rate should be quoted both in words and figures. The job should be started within 7 days and completed within 30 days from the date of receipt of Work Order.

1/3



1, क्वीन्स वे, कोलकाता - 700 071  
1, Queen's Way, Kolkata - 700 071

# विक्टोरिया मेमोरियल हाल

## VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण  
के तहत एक स्वायत्त संगठन)

(An autonomous organisation under the administrative control  
of the Ministry of Culture, Govt. of India)

The tenderers should have sufficient experience in doing similar nature of jobs preferably in Govt. Sector. The tenderers should submit photocopies of their licences, PAN card, GSTIN (GSTR-1, GSTR-3B) documents and papers in support of their work experience.

The tenderers will be required to deposit 3% of the quoted rates as Earnest Money in the form of Demand Drafts in favour of the "Victoria Memorial Hall", drawn from any commercial bank, payable at Kolkata. However, the tenderers who are exempted from furnishing EMD as per GOI orders need not furnish EMD, subject to submission of necessary supporting papers. The above earnest money will be refunded after one month from the date of issuance of Work Order. The EMD's of unsuccessful tenderers shall be released after the issuance of work order or latest by one month

The successful tenderer will be required to deposit 10% of the total work value as Security Deposit in the same form in which the Earnest money has been deposited to the Victoria Memorial Hall before receiving of Work Order. The security money since deposited will be refunded not earlier than Eight month from the date of completion of the job. The earnest money will be forfeited if the Security Money is not deposited within seven days from the date of intimation in this regard or if the successful tenderer is unable to commence the job within specified time. The Security Money will be forfeited if the allotted work is not started within seven days from the date of intimation or completed within scheduled time frame.

The job executed by the successful tenderer shall have to be guaranteed against bad workmanship for a period of six (6) months from the date of completion of the job. If any defect is detected during the period as mentioned above, he will be liable to rectify the same free of cost within reasonable time. Otherwise, VMH will get it rectified at its own cost and adjust the same from the Security Deposit.

The job to be executed is scheduled to be inspected by the concerned unit of the VMH.

2/3

☎ : 2223-1890/1891/0953/5142 • फैक्स/Fax : +91-33-2223-5142

ई-मेल/E-mail : victomem@gmail.com • वेबसाइट/Website : www.victoriameorial-cal.org





1, क्वीन्स वे, कोलकाता - 700 071  
1, Queen's Way, Kolkata - 700 071

विक्टोरिया मेमोरियल हाल

VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण  
के तहत एक स्वायत्त संगठन)

(An autonomous organisation under the administrative control  
of the Ministry of Culture, Govt. of India)

The job to be executed will follow the Govt. specification.

The payment against the allotted work shall be released as per actual measurement and work done.

For any additional information, tenderers may contact the In-charge of Electric Unit VMH between 2:00 pm to 4:00 pm on any working day.

The authority reserves the right to accept or reject any or all the tenders without assigning any reason thereof.

**The tenderers are advised to inspect the feasibility of nature of the work/ job to be executed prior to submission of tender very carefully. Any complexity arisen during/ after commencement of the job would not be entertained at this end and the tenderer (successful) should have to complete the work as per schedule of the work.**

Encl: One Schedule of Work .

  
Secretary & Curator

Copies along with Schedules of Work forwarded to the Security Officer for kind information and Shri Dipankar Samantha with request to upload the NIT in the website of VMH and Govt. Portal .

  
Secretary & Curator

3/3

☎ : 2223-1890/1891/0953/5142 • फैक्स/Fax : +91-33-2223-5142

ई-मेल/E-mail : victomem@gmail.com • वेबसाइट/Website : www.victoriameorial-cal.org

Annexure-1

Schedule of Work

Name of Work:

Supply, laying and fixing of 200 sqmm underground armoured aluminium cable T1 switch room to T1 panel located inside the Victoria Memorial building premises, Kolkata.

S. No.	Description of work	Qty	Rate	Amount
01	Supply of 3.5 core, 200 sqmm size of PVC insulated and PVC sheathed/ XLPE armoured aluminium conductor cable of 1.1 KV grade	350 Mtrs (Approx.)		
02	Laying of one no. PVC insulated and PVC sheathed/ XLPE power cable of 1.1 kv grade, direct in ground including cutting the concrete pathway and making good the damages. excavation, protective covering and refiling the trench etc. as required.	200 Mtrs approx		
03	Supply and making end termination with brass compression gland and aluminium lug for following size of PVC insulated and PVC sheathed/ XLPE aluminium Conductor armoured cable of 1.1 KV grade as required 3.5 core 200 sqmm.	02 Nos		
04	Providing & fixing 80 mm dia medium class GI pipe ISI marked for cable protection at gravel area and road crossing i/c cutting of concrete pathways and refilling the same making good the damages	20 Mtrs		
05	Dismantling of damaged 150 sqmm, aluminium armoured cable on surface/ recess	01 Job		