

1, क्वीन्स वे, कोलकाता - 700 071 1, Queen's Way, Kolkata - 700 071 विक्टोरिया मेमोरियल हाल VICTORIA MEMORIAL HALL

(भारत सरकार के संस्कृति मंत्रालय के प्रशासनिक नियंत्रण के तहत एक स्वायत्त संगठन)

(An autonomous organisation under the administrative contol of the Ministry of Culture, Govt. of India)

VMNo. 731

/2024

10.05.2024

## **Tender Notice**

Victoria Memorial Hall, 1 Queen's Way, Kolkata 700071 (2223 0953) invites tender from the reputed/sufficient experienced civil contractors who has done similar types of works for repair and painting of garden benches at Victoria Memorial premises (as per schedule of works). The tender in sealed cover should be superscribed with "Tender for repair and painting of garden benches" must be sent to the Secretary & Curator, Victoria Memorial Hall within 01 p.m. on 31.05:2004 Tenderers are to submit documents about their experience, Pan Card, GST certificate, Trade licence, Audited Accounts of last three years (all photo copies) alongwith tenders.

The tenders will be opened on the same day at 2.30 p.m. in the chamber of the Accounts officer. Tenderers/their representatives may remain present at the time of opening of tender if they so desire.

The tender should be accompanied by an EMD @ 2% of the estimated value of Rs.6,08,130.00 in the form of an a/c payee Demand Draft drawn in favour of "Victoria Memorial Hall' payable at Kolkata. However the tenderers who are exempted from furnishing EMD as per GOI orders, need not furnish EMD, subject to submission of necessary supporting documents. The Successful bidder will have to deposit performance security @ 5% of the value of the contract, which should remain valid for a period of sixty days beyond the date of completion of all contractual obligations of the agency including warranty obligations.

The rate should be submitted in the prescribed format. The rates inclusive of taxes & charges should be quoted both in words and figures. The rate quoted will be valid for six months. The successful tenderer will be required to complete the job within 60 days of the receipt of the work order. The work should be done with good quality ISI marked materials under the supervision of the Security Officer. Tenderers may inspect the site on any working day, during working hours, before submission of tenders.

VMH reserves the right of rejection of any or all tenders without assigning any reason.

Secretary & Curator

Copy forwarded:

The Accounts Officer, VM

Shri Dipankar Samanta is requested to upload the matter on VM website.

Shri Nilanjan Sinha is requested to upload the matter on CPP portal

Secretary & Curator

🕡 : 2223-1890/1891/0953/5142 • फैस्प/Fax :+91-33-2223-5142

ई-मेल/E-mail : victomem@gmail.com ● वेबसाइट/Website : www.victoriamemorial-cal.org

## Victoria Memorial Hall Kolkata

## Schedule of quantities

	DSR'21	air & painting on garden bench at VMH, Kolkata during	Quantity	unit	Rate	Amount
em No.	Item no	Description of items				
1	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:				
1.1	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	12.00	Cum	9867.52	118410.24
2	9.1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).				
2.1	9.1.2	Sal wood	0.70	Cum	142980.45	100086.32
3	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
3.1	15.23.1	For thickness of tiles 10 mm to 25 mm	150.00	sqm	81.06	12159.00
4	13.62	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:				
4.1	13.62.1	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand		Sqm	256.43	320537.50
5	1.1.18	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge.  Note - item to be applicable in urban areas having directions for restricted hours for movement/ plying of load carrying motor vehicle of 3.5 cum or more.	10.00	Cum	551.04	5510.40
6	M.R	Providing and placing 23mm thick Ultra or equivalante Paver tiles of approved quality size and shape in footpath & courtyard jointed with near cement slurry mixed with pigment to match the shade of tiles including rubbing and cleaning etc. complete on 20 mm thick bed of cement mortar 1:4 (1 cement 4 coarse sand ) Any shade pigment with whit cement.	20.00 t	sqm	2571.32	51426.40

Total Rs.= 608129.86

Say, Rs 6,08,130.00